



AGENDA

The City of Beaufort

HISTORIC DISTRICT REVIEW BOARD

Wednesday, October 14, 2020, 2:00 P.M.

~~City Hall, Planning Conference Room — 1911 Boundary Street, Beaufort, SC~~

Please click the link below to join the webinar:

<https://us02web.zoom.us/j/83615703724?pwd=U3FaSHJORkU3R2o4cWl6RXhoTXdtZz09>

Password: 493391

Meeting ID: 836 1570 3724

Call in Phone# 1+929 205 6099

STATEMENT OF MEDIA NOTIFICATION: “In accordance with South Carolina Code of Laws, 1976, Section 30-4-80(d), as amended, all local media were duly notified of the time, date, place, and agenda of this meeting.”

Note: A project will not be reviewed if the applicant or representative is not present at the meeting.

- I. Call to Order:
- II. Approval of Minutes:
 - A. September 9, 2020 Meeting
- III. Old Business:
 - A. Rules of Procedure for the Conduct of Business
 - B. 510 Craven Street, Renovation/Addition
Applicant: Ansley Manuel (20-33 HRB.2)
The applicant is requesting preliminary approval for a renovation/addition to the carriage house in the rear of the property at 510 Craven Street.
- IV. New Projects:
 - A. 804 Harrington Street, New Construction
Applicant: Jeremiah Smith (20-42 HRB.1)
The applicant is requesting final approval for new construction of single-family dwelling at 804 Harrington Street.
 - B. 1711 King Street, Roof Replacement
Applicant: Lorraine Yaralian (20-45 HRB.1)
The applicant is requesting final approval of a roof replacement at 1711 King Street.
- V. Adjournment



Historic District Review Board

Meeting Minutes – July 8, 2020

1 CALL TO ORDER

0:56

A meeting of the Historic District Review Board was held via Zoom on Wednesday, July, 8 2020.

2 ATTENDEES

Members in attendance: John Dickerson (Chairman), Bill Allison (Vice-Chair), Katherine Pringle, and Chuck Symes.

Staff in attendance: Jeremy Tate (Meadors Architecture), Heather Spade (City of Beaufort Planning Tech of Community and Economic Development), and David Prichard (City of Beaufort Director of Community and Economic Development).

Motion: Mr. Symes made a motion to move the last item on the agenda to the to be the first item on the agenda; seconded by Ms. Pringle. The motion passed unanimously. **1:13**

3 REVIEW OF MINUTES

1:55

Motion: Ms. Pringle made a motion to approve the April 8, 2020 minutes as submitted; seconded by Mr. Symes. The motion passed unanimously.

Motion: Mr. Symes made a motion to approve the June 10, 2020 minutes as submitted; seconded by Ms. Pringle. The motion passed unanimously.

Motion: Mr. Symes made a motion to approve the June 17, 2020 Special Meeting minutes as submitted; seconded by Ms. Pringle. The motion passed unanimously.

All Historic District Review Board Meeting minutes are recorded, and can be found on the City's website at <http://www.cityofbeaufort.org/AgendaCenter>. Audio recordings are available upon request by contacting the City Clerk, Ivette Burgess at 843-525-7018 or by email at iburgess@cityofbeaufort.org.

4 REVIEW OF FULL BOARD PROJECTS

3:27

- A. Johan Niemand from JHN-Residential Building Design, on behalf of James and Eileen White, had applied for alterations and additions to the existing structure at 521 New Street, R120 004 000 0737 0000.

Motion: Mr. Symes made a motion to grant final approval based on the City Staff's recommendations as well as the Board's comments; seconded by Mr. Allison. The motion passed unanimously.

- B. Andrew Rogerson from Garvin Design Group, on behalf of Wheeler & Wheeler, **9:10** had applied for an application requesting alterations to the existing jail building located at 1409 King Street, R120 004 000 1009 0000.

Motion: Mr. Symes made a motion to grant preliminary approval to the renovation of the jail building with the parking issues to be resolved; seconded by Ms. Pringle. The motion passed unanimously.

- C. Andrew Rogerson from Garvin Design Group, on behalf of Wheeler & Wheeler, **33:40** had applied for an application requesting new construction of 4 attached dwelling units located at 1409 King Street, R120 004 000 1009 0000.

Motion: Mr. Symes made a motion to defer the new construction project at 1409 King Street; seconded by Ms. Pringle. The motion passed with 3:1; Mr. Dickerson being opposed. **2:05:29**

5 OLD BUSINESS

2:07:58

- A. Joel Newman from Thomas and Denzinger Architects, on behalf of Richard Callari, had applied for alterations to convert the existing building into a 12-unit hotel located at 501 Carteret Street, R120 004 000 0731 0000.

Motion: Mr. Dickerson made a motion to grant final approval as submitted; seconded by Mr. Allison. The motion passed unanimously.

6 ADJOURNMENT

2:49:11

Motion: Ms. Pringle made a motion to adjourn the meeting; seconded by Mr. Allison. The motion passed unanimously.

Chair

Date of approval



Historic District Review Board

RULES OF PROCEDURE FOR THE CONDUCT OF BUSINESS

Proposed New Document 7.27.2020

These Rules of Procedure are adopted by the City of Beaufort Historic Design Review Board in accordance with the provisions of S.C. Code 6-29-870 and section 10.7.4.D.1 of The Beaufort Code, The City of Beaufort, SC, adopted June 27, 2017, amended July 10, 2018.

Section 1. - Rules of Order

Robert's Rules of Order shall govern the conduct of meetings except as otherwise provided by these Rules of Procedure.

Section 2. – Conduct of Hearing

The normal order of hearing, subject to modification by the Chairman, shall be:

- A. ~~Statement of~~ The Chairman introduces the matter to be heard – *project address and applicant request, i.e.: conceptual, preliminary, or final approval* (~~Chairman~~);
- B. Staff introduction of the project, providing the context and historic background (~~5 minutes~~^[1]);
- C. Response Statement by the applicant, ~~or in the case of an appeal, the~~ administrative^[2] officer (normally about 5 minutes);
- D. Public comment (~~7-minute limit total~~ – Normally limited to about^[3] 2 minutes per person, or as determined by the Chairman),
- E. Public comments closed;
- F. Applicant responses to the board regarding public comment (Normally about 5 ~~3~~^[4] minutes);
- G. Public comments closed;
- H. **Staff recommendation to Board;**
- I. Applicant points of clarification to the board in response to the staff recommendation (Normally about 3 minutes);
- J. Full Board discussion, ~~no public or applicant comment. Board Members may ask an applicant direct questions. Applicant may respond to specific questions, but this is not an opportunity for applicant to make additional points; (All board members are given the opportunity to speak before any individual members speaks twice) ref. RR.LO obtaining and assigning the floor~~ – The Chairman will ensure that each member of the Board has an opportunity to express their views about the project.

- K. Board action, no public or applicant comment. ~~Board must take action.~~ [5] The Chairman will call for a motion. Each Board member will be individually polled as to how they vote.

Section 3. Additional Rules for Conducting Virtual Meetings

- A. The Chairman will identify a Staff member who has the responsibility of monitoring comments by the public and ensuring that the Board hears those comments.

Section ~~3~~ 4. Adoption.

These rules and regulations were adopted by vote of a majority of the members of the HRB at a regular public meeting on _____.



Historic District Review Board

RULES OF PROCEDURE FOR THE CONDUCT OF BUSINESS

Proposed New Document 9.29.2020

These Rules of Procedure are adopted by the City of Beaufort Historic Design Review Board in accordance with the provisions of S.C. Code 6-29-870 and section 10.7.4.D.1 of The Beaufort Code, The City of Beaufort, SC, adopted June 27, 2017, amended July 10, 2018.

Section 1. - Rules of Order

Robert's Rules of Order shall govern the conduct of meetings except as otherwise provided by these Rules of Procedure.

Section 2. – Conduct of Hearing

The normal order of hearing, subject to modification by the Chairman, shall be:

- A. The Chairman introduces the matter to be heard – *project address and applicant request, i.e.: conceptual, preliminary, or final approval;*
- B. Staff introduction of the project, providing the context and historic background;
- C. Statement by the applicant (normally about 5 minutes);
- D. Public comment (Normally limited to about 2 minutes per person or as determined by the Chairman);
- E. Public comments closed;
- F. Applicant responses to the board regarding public comment (Normally about 5 minutes);
- G. Staff recommendation to Board;**
- H. Applicant points of clarification to the board in response to the staff recommendation (Normally about 3 minutes);
- I. Full Board discussion. *Board Members may ask an applicant direct questions. Applicant may respond to specific questions, but this is not an opportunity for applicant to make additional points. The Chairman will ensure that each member of the Board has an opportunity to express their views about the project.*
- J. Board action, no public or applicant comment. *The Chairman will call for a motion. Each Board member will be individually polled as to how they vote.*

Section 3. Additional Rules for Conducting Virtual Meetings

- A. *The Chairman will identify a Staff member who has the responsibility of monitoring comments by the public and ensuring that the Board hears those comments.*

Section 4. Adoption.

These rules and regulations were adopted by vote of a majority of the members of the HRB at a regular public meeting on _____.

CITY STAFF INTRODUCTION

510 CRAVEN STREET



PROJECT LOCATION - 510 CRAVEN STREET









**BEAUFORT COUNTY
HISTORIC SITES SURVEY - 1997**

INTENSIVE LEVEL BUILDING INVENTORY FORM

Statewide Survey Site Form
State Historic Preservation Office
South Carolina Department of Archives and History
Columbia, SC

Site Number: U- 13 - 824
Access County Site #
USGS Quad: 025 Beaufort
Doc. Level: Intensive Level-Building

Historic name(s): _____ Map Ref.: BFT 09 (BR) Tax Number: R120 004 000 0837 0000
Common name(s): _____ City Block Ref.: 26 .04 Island: Port Royal Is.
Address/location: 501 Craven St. City/Vicinity of (vic.): Beaufort
Date: 1886 ca. Alteration date: _____
Ownership: 1. private 2. city 3. county 4. state 5. federal 6. unknown
Category: 1. building 2. site 3. structure 4. object
Historic use(s): single dwelling Current uses: single dwelling

National Register Status: _____ Date: _____ Listing Name: _____ NRIS # _____
National Register Historic District (NHL, 11/73) 12/17/69 Beaufort Historic District 69000159

SHPO National Register Evaluation: Contributes to listed district Name: Beaufort Historic District

Consultant Recommendation: _____ Name: _____

Previous Survey:

- H.A.B.S.
 Feiss-Wright (1969)
 Historic Resources of the Lowcountry (1979)
 Milner Historic District Inventory (1979)
 A Guide to Historic Beaufort (1995 ed.)

Reference:

Other
026 - 837
38 BU 1033
026 (837) -3

Notes:

4 Worthy of Mention
The Point
Vol. 07: full form

Photograph:



Photographs:

- prints
 slides
 negatives

Date: 9-4-97


Recorder: C. Brooker, Brooker Arch. Cons.

Roll # Neg. View of:
B-10 35 South facade

Style: Folk Victorian Commercial Form:
 Core Shape: rectangular Stories: 2 stories Construction: frame
 Roof: Shape: gable (end to front) Material: not visible
 Chimney: Type: not visible Material:
 Exterior Walls: weatherboard
 Windows: single Type: double hung Pane 2/2
 Config.:
 Doors: Foundation: stuccoed masonry
 Porch Height: Porch Width: entrance bay only Porch Roof Shape: Stoop
 Porch Details: Stoop Decorative Elements:
 Outbuildings: none Interior Features:
 Number of Related Resources:
 Surroundings: residential Acreage: Less than one Quadrangle: Beaufort
 Alterations: Alteration date: Integrity: good Condition: good

Description: Rectangular 2 story end gable framed dwelling, one of three very similar adjoining structures. The main facade faces south, 3 bay with door right, bay window left at first floor level. Entrance protected by stoop only.

Historical Data: Built by E. A. Scheper c. 1886



Site Number: U - 13 - 824

Informant/ Bibliography: General George Crist unpublished history.

APPLICANT PRESENTATION

510 CRAVEN STREET



DEVELOPMENT REVIEW PROCESS
HISTORIC REVIEW BOARD APPLICATION

Community & Economic Development Department
1911 Boundary Street, Beaufort, South Carolina, 29902
p. (843) 525-7011 / f. (843) 986-5606
www.cityofbeaufort.org

* fee paid at Aug. Submitted

Staff Review
 Board Review

Application Fee:
see attached schedule

20-33 HRA. 2

OFFICE USE ONLY: Date Filed: 9/10 Application #: 21002 Zoning District: 74-HIV
BCAGHS Survey: Yes No

Schedule: The Historic Review Board (HRB) typically meets the 2nd Wednesday of each month at 2pm. The complete schedule, along with the list of deadlines, may be found here - <http://www.cityofbeaufort.org/historic-review-board.aspx>

Submittal Requirements: All forms and information shall be submitted digitally. In addition to a complete application form, applicants shall submit the required items according to the checklists on the subsequent page.

Review Request: Conceptual Preliminary Final Bailey Bill Approval* Change After Certification
*Requires a Bailey Bill - Part A Preliminary Review Application Form

Pursuant to Section 6-29-1145 of the South Carolina Code of Laws, is this tract or parcel restricted by any recorded covenant that is contrary to, conflicts with, or prohibits the activity described in this application? Yes No

Applicant, Property, and Project Information

Applicant Name: Ansley H. Manuel, Architect
Applicant Address: 104 Pritchard Street Bluffton, S.C. 29910
Applicant E-mail: manuel.studio@aol.com Applicant Phone Number: 843.338.8932

Applicant Title: Homeowner Tenant Architect Engineer Developer

Owner (if other than the Applicant): Marcellene Trask

Owner Address: 6 Meeting Street Beaufort, S.C. 29902

Project Name: Marcellene Trask Guest House

Property Address: 510 Craven Street

Property Identification Number (Tax Map & Parcel Number): R 120.004.000.0890.0000

Date Submitted: Emailed 9/10/2020

Certification of Correctness: I/we certify that the information in this application is correct.

Applicant's Signature: [Signature] Date: 10 September 2020

Owner's Signature: Marcellene Trask Date: 9.10.20

(The owner's signature is required if the applicant is not the owner.)

Required Project Information

See Section 9.10 of the Beaufort Code for complete information about Certificates of Appropriateness and Section 10.7 for complete information about the Historic Review Board | This form is also available online at www.cityofbeaufort.org | updated February 5, 2019



DEVELOPMENT REVIEW PROCESS
HISTORIC REVIEW BOARD APPLICATION

Community & Economic Development Department
1911 Boundary Street, Beaufort, South Carolina, 29902
p. (843) 525-7011 / E. (843) 986-5606
www.cityofbeaufort.org

Project Name: Marcellene Trask Guest House

Property Size in Acres: .15 Proposed Building Use: Guest House

Nature of Work (check all that apply):

- Checkboxes for New Construction, Primary Structure, Alterations / Additions, Demolition*, and Relocation*.

Building Square Footage (if multiple buildings, please list each one and their square footage by floor):

PROPOSED 595 Heated / 68 porch EXISTING 561 Heated / 0 porch

Is this project a redevelopment project: Y N

Are there existing buildings on the site? Y N if yes, will they remain? Y N

Provide a brief Project Narrative (if requesting Bailey Bill Approval, this section may be left blank):

The applicant proposes two phases of construction for the property at 510 Craven Street. The first previously-approved phase will be the interior renovations, reroof and change of exterior colors to the main residence. The second phase will be the guest house renovation.

The guest house is shown on the 1899 Sanborn Insurance Fire Map as a 13'6" x 14'6" accessory building. Some point later two additions were added - a bath and closet on the north end and living room on the south end.

The carriage house renovations are extensive. First, the building will have all later additions mostly removed with only the original structure and bath/closet roof remaining. Second, the building will be raised as it currently sits well below flood level. The raising of the house will be coordinated to match the height of the main house bottom bandboard. Lastly, an entry porch will be added to the north end and bedrooms and bath to the south end. All exterior colors will match the main house.

CONTACT INFORMATION -

Attention: Julie A. Bachety, Administrative Assistant II

City of Beaufort Department of Planning & Development Services

1911 Boundary Street, Beaufort, South Carolina 29902

E-Mail: jbachety@cityofbeaufort.org | Phone: (843) 525-7011 | Fax: (843) 986-5606

**BEAUFORT COUNTY
HISTORIC SITES SURVEY - 1997**

INTENSIVE LEVEL BUILDING INVENTORY FORM

Statewide Survey Site Form
State Historic Preservation Office
South Carolina Department of Archives and History
Columbia, SC

Site Number: U- 13 - 824
Access County Site #
USGS Quad: 025 Beaufort
Doc. Level: Intensive Level-Building

Historic name(s): _____ Map Ref.: BFT 09 (BR) Tax Number: R120 004 000 0837 0000
Common name(s): _____ City Block Ref.: 26 .04 Island: Port Royal Is.
Address/location: 501 Craven St. City/Vicinity of (vic.) Beaufort
Date: 1886 ca. Alteration date: _____
Ownership: 1. private 2. city 3. county 4. state 5. federal 6. unknown
Category: 1. building 2. site 3. structure 4. object
Historic use(s): single dwelling Current uses: single dwelling

National Register Status: _____ Date: _____ Listing Name: _____ NRIS # _____
National Register Historic District (NHL, 11/73) 12/17/69 Beaufort Historic District 69000159

SHPO National Register Evaluation: Contributes to listed district Name: Beaufort Historic District

Consultant Recommendation: _____ Name: _____

Previous Survey:

- H.A.B.S.
 Feiss-Wright (1969)
 Historic Resources of the Lowcountry (1979)
 Milner Historic District Inventory (1979)
 A Guide to Historic Beaufort (1995 ed.)

Reference:

Other
026 - 837
38 BU 1033
026 (837) -3

Notes:

4 Worthy of Mention
The Point
Vol. 07: full form

Photograph:



Photographs:

- prints
 slides
 negatives

Date: 9-4-97

Recorder: C. Brooker, Brooker Arch. Cons.


Roll # Neg. View of:
B-10 35 South facade

Style: Folk Victorian Commercial Form:
 Core Shape: rectangular Stories: 2 stories Construction: frame
 Roof: Shape: gable (end to front) Material: not visible
 Chimney: Type: not visible Material:
 Exterior Walls: weatherboard
 Windows: single Type: double hung Pane 2/2
 Config.:
 Doors: Foundation: stuccoed masonry
 Porch Height: Porch Width: entrance bay only Porch Roof Shape: Stoop
 Porch Details: Stoop Decorative Elements:
 Outbuildings: none Interior Features:
 Number of Related Resources:
 Surroundings: residential Acreage: Less than one Quadrangle: Beaufort
 Alterations: Alteration date: Integrity: good Condition: good

Description: Rectangular 2 story end gable framed dwelling, one of three very similar adjoining structures. The main facade faces south, 3 bay with door right, bay window left at first floor level. Entrance protected by stoop only.

Historical Data: Built by E. A. Scheper c. 1886


Sketch:



Site Number: U - 13 - 824

Informant/ Bibliography: General George Crist unpublished history.

RENOVATIONS TO THE MARCELLE TRASK GUEST HOUSE
 510 CRAVEN STREET BEAUFORT, SOUTH CAROLINA
 MANUEL STUDIO, LLC, ANNELEY H. MANUEL, ARCHITECT, 843.338.8992




EXISTING SITE PLAN SCALE OF 1" = 20'-0"

EXISTING PERVIOUS/IMPERVIOUS
 51% / 49%


PROPOSED PERVIOUS/IMPERVIOUS
 57% / 43%

CRAVEN STREET



PROPOSED SITE PLAN SCALE OF 1/8" = 1'-0"


30 JUNE 2020
 10 SEPT 2020
 22 SEPT 2020




EXISTING NORTH ELEVATION SCALE OF $\frac{1}{4}'' = 1'-0''$



EXISTING EAST ELEVATION SCALE OF $\frac{1}{4}'' = 1'-0''$



EXISTING SOUTH ELEVATION SCALE OF $\frac{1}{4}'' = 1'-0''$




EXISTING FLOOR PLAN SCALE OF $\frac{1}{4}'' = 1'-0''$



EXISTING WEST ELEVATION SCALE OF $\frac{1}{4}'' = 1'-0''$

RENOVATIONS TO THE MARCELLENE TRASK GUEST HOUSE
 510 CRAVEN STREET BEAUFORT, SOUTH CAROLINA
 MANUEL STUDIO, LLC, ANSLEY H. MANUEL, ARCHITECT, 843.3888792




PROPOSED FOUNDATION PLAN SCALE OF $\frac{1}{4}'' = 1'-0''$



PROPOSED NORTH ELEVATION SCALE OF $\frac{1}{4}'' = 1'-0''$

RENOVATIONS TO THE MARCELENE TRASK GUEST HOUSE
 510 CRAVEN STREET BEAUFORT, SOUTH CAROLINA
 MANUEL STUDIO LLC, ANGELEY H. MANUEL, ARCHITECT, 843.338.8932



PROPOSED FLOOR PLAN SCALE OF $\frac{1}{4}'' = 1'-0''$



PROPOSED WEST ELEVATION SCALE OF $\frac{1}{4}'' = 1'-0''$

- MATCH MAINHOUSE METAL ROOF
- 5" EXPOSURE CLAPBOARD HORIZONTAL SIDING
- 9" EXPOSURE SHIPLAP HORIZONTAL SIDING
- LOUVERS
- STUCCO FINISH



PROPOSED SOUTH ELEVATION SCALE OF $\frac{1}{4}'' = 1'-0''$




PROPOSED EAST ELEVATION SCALE OF $\frac{1}{4}'' = 1'-0''$

RENOVATIONS TO THE MARCELENE TRASK CARRIAGE HOUSE
 510 CRAVEN STREET BEAUFORT, SOUTH CAROLINA
 MANUEL STUDIO, LLC, ANNEVEY H. MANVEL, ARCHITECT, 843.338.8732

4

30 JUNE 2020
 10 SEPT 2020



HAND GREASE PAINTED METAL ROOF
 (1" HIGH SEAM @ 17 1/4" O.C.) OVER 30# FELT
 OVER 1/2" OX PLYWOOD OVER 2x8 @ 16" O.C.
 RAFTERS WITH HURRICANE STRAPS - SIMPSON MTS 60

MATCH EXISTING FACIA, SOFFIT
 AND CORNICE MATERIALS + DETAILS

2x4 BRACING BEHIND PLYWOOD SHEATH

5" EXPOSURE CLAPBOARD HORIZONTAL
 SIDING OVER HOUSEWRAP OVER 1/2" OX
 PLYWOOD OVER 2x4 @ 16" O.C. WALL STUDS

SPRAY FOAM INSULATION R-13 VALUE MINIMUM

CONTINUOUS TIE DOWN FROM CMU EMBEDMENT
 TO TOP OF PLATE @ ALL CORNERS, OPENINGS + 32" O.C.

AT OR BELOW MAINHOUSE BANDBOARD + DRIPCAP

MATCH MAINHOUSE BANDBOARD

P.T. 2x8 GILL WITH TERMITESHIELD

TOP COURSE WITH (1) #5

8" CMU FOUNDATION WALL WITH
 (1) #5 VERTICAL REBAR

CONCRETE FOOTING W/ (3) #5 REBAR

CLEAN, COMPACT AND TREATED SOIL

WOOD FLOOR FINISH OVER
 3/4" OVERFLOOR OVER
 2x8 @ 16" O.C.
 FLOOR JOISTS

HVAC ZONE

18" O" ANGLE

WALL SECTION SCALE OF 1" = 1'-0"

RENOVATIONS TO THE MARCELLENE TRASK GUESTHOUSE
 510 CRAVEN STREET BEAUFORT, SOUTH CAROLINA
 MANUEL STUDIO, LLC, ANSLEY H. MANUEL ARCHITECT, 843.338.8732

Marcellene Trask
6 Meeting Street
Beaufort, SC
29907
marcellenetrask@yahoo.com

Dated September 10, 2020

List of Paint Color Choices for 510 Craven Street Carriage House, Beaufort, SC 29902

Exterior and foundation:	Farrow & Ball Borrowed Light 235
Lattice work between foundation piers:	Farrow & Ball Banacha 298
Exterior Door:	Farrow & Ball Banacha 298
All Trim including porch railings, porch columns, window sashes, and balustrade:	Farrow & Ball Cabbage White 269
Porch Ceilings:	Farrow & Ball Lulworth Blue 89
Porch Floor:	Farrow & Ball Pavilion Gray 242

Regarding the Roof:

The same roof as the main house – metal, hand seamed in Slate Gray.





Done

8 of 17














COLOR SCHEME



NEW STREET ELEVATION

SCALE OF 1/8" = 1'-0"

RENOVATIONS TO THE MARCELLENE TRASK GUNBOAT HOUSE
 510 CRAVEN STREET BEAUFORT, SOUTH CAROLINA
 MANUEL STUDIO, LLC, ANKLEY H. MANUEL, ARCHITECT ©2013, 2012



DEMO PLAN

RENOVATIONS TO THE MARGHERITE TRASK CARPENTERS HOUSE
 510 CRAVEN STREET BEAUFORT, SOUTH CAROLINA
 MANUEL STUDIO, LLC, ANSLEY H. MANUEL, ARCHITECT, 843.398.8932



Historic Review Board Meeting Staff Report

From the Department of Community and Economic Development
14 October 2020

1 SUMMARY OF REQUEST

510 Craven Street, Renovation/addition

Applicant: Ansley Manuel (20-33 HRB.2)

The applicant is requesting preliminary approval for a renovation/addition to the carriage house in the rear of the property at 510 Craven Street.

This is a contributing structure in the Historic Preservation Neighborhood.

Background: The Applicant submitted two applications for this address that were reviewed at the August 2020 HRB Meeting. The first application was for final approval of a re-roof and exterior color change of the main residence on the property. This application was approved for final with noted changes to the exterior color palate and a hand crimp seam on the new roof. The Second application was for preliminary approval for renovations to the carriage house on the property. This application was deferred.

2 FACTS

Property Address:	510 Craven Street
Parcel ID:	R120 004 000 0890 0000
Case Number:	20-33 HRB.2
Applicant:	Ansley Manuel
Zoning:	T4-HN
Use:	Single Family Dwelling

District Development Standards for T4-HN:

- **Setback requirements – Accessory Structure:**
 - *Accessory structures shall be located behind the front façade of the primary structure.*
 - *Rear setback – 5' min.*
 - *Side Corner/Alley – 5' min.*
 - *Side Interior – 5' min.*
- **Impervious Surface Coverage:** 55% maximum
- **Current Flood Zone:** A11, Base Flood Elevation: +13', with 1' freeboard required by City of Beaufort



References:

- Beaufort Preservation Manual Supplement, Chapter 3: New Construction, Additions, Demolition, and Signage
- Beaufort Preservation Manual Supplement, Chapter 7: Doors, Windows, Shutters

- Beaufort Preservation Manual, p. 80-81: Foundation Infill
- Secretary of the Interior's Standards for Treatment of Historic Properties

3 STAFF COMMENTS/ RECOMMENDATIONS

1. Per previous application discussion, it has been established that the original Carriage House was built between 1899 and 1894, therefore, the original footprint of the Carriage House is historic. The two additions to the Carriage House are not historic. Staff supports their removal.
2. Per previous application discussion, staff supports lifting the existing carriage house structure to match the existing Finish Floor Elevation of the Main House, which the applicant is proposing to alleviate flooding concerns.
3. Overall, this is a positive addition to the existing historic carriage house at 510 Craven Street. The addition is appropriately massed so that it is compatible yet distinct from the original structure.
4. The applicant is proposing the use of shiplap siding on that portion of the addition that directly attaches to the historic carriage house structure which is appropriate and complies with Chapter 3 of the Beaufort Preservation Manual Supplement. However, the applicant is proposing lap siding (to match existing historic carriage house siding) at the southern two-bedroom volume. Staff recommends that all new construction is clad with shiplap to differentiate new construction from the original historic carriage house footprint.
5. Staff supports the applicant's proposed removal of the northern non-historic bathroom wing of the existing carriage house and replacing this area with an open porch. This is a positive approach and gives the carriage house a better-defined entry point that is still subordinate to the main structure.
6. Staff supports the sizes and locations of the new windows on the addition in that they match the size and proportion of the existing carriage house windows. Applicant to ensure and demonstrate in future submissions that the new windows are compliant with p. 37 of the Beaufort Preservation Manual Supplement: "only clear glass should be used in any window in the Historic District, and only true muntins may be used on all proposed wood windows in the Historic District.
7. Staff supports the design of the new entry door to the Carriage house. In future submissions, applicant to ensure and demonstrate compliance with pages 35 and 36 of the Beaufort Preservation Manual Supplement regarding doors.
8. Staff supports the louvered design between the foundation piers. When detailing this design, applicant to ensure compliance with pages 80 and 81 of the Beaufort Preservation Manual regarding Foundation infill.
9. The color choices for the exterior are appropriate and match the previously approved colors of the main house.


10. Staff supports the replacement of the existing standing seam roof with a new standing seam roof to match the main house new roof. As discussed with the main house roof application in the August meeting, the carriage house standing seam roof should have hand-seamed hip, ridge, and other termination elements – no hip caps, ridge caps, or other bulky terminations. Applicant to include details for roofing in future submissions. It is the Applicant/roof contractor's responsibility to select appropriate metal roofing material suitable for hand folding at ridges, hips, and terminations.

STAFF RECOMMENDATION:

Preliminary Approval with conditions noted.

CITY STAFF INTRODUCTION


804 HARRINGTON STREET



PROJECT LOCATION - 804 HARRINGTON STREET

810 HARRINGTON

811 HARRINGTON



800 HARRINGTON

803 HARRINGTON



CONTEXT



SITE - HARRINGTON ST. & CROFUT LN.

908 HARRINGTON



810 HARRINGTON



910 HARRINGTON
HARRINGTON STREET CONTEXT



1301 WASHINGTON

803 HARRINGTON



1215 PRINCE



811 HARRINGTON
HARRINGTON STREET CONTEXT



800 HARRINGTON

APPLICANT PRESENTATION

804 HARRINGTON STREET



DEVELOPMENT REVIEW PROCESS
HISTORIC REVIEW BOARD APPLICATION

Community & Economic Development Department
1911 Boundary Street, Beaufort, South Carolina, 29902
p. (843) 525-7011 / f. (843) 986-5606
www.cityofbeaufort.org

- Staff Review
Board Review

Application Fee:
see attached schedule

20-42 HRB.1

OFFICE USE ONLY: Date Filed: 9/16 Application #: 21026 Zoning District: T4-HN
BCAGHS Survey: Yes No

Schedule: The Historic Review Board (HRB) typically meets the 2nd Wednesday of each month at 2pm. The complete schedule, along with the list of deadlines, may be found here - http://www.cityofbeaufort.org/historic-review-board.aspx

Submittal Requirements: All forms and information shall be submitted digitally. In addition to a complete application form, applicants shall submit the required items according to the checklists on the subsequent page.

Review Request: Conceptual Preliminary Final Bailey Bill Approval* Change After Certification
*Requires a Bailey Bill - Part A Preliminary Review Application Form

Pursuant to Section 6-29-1145 of the South Carolina Code of Laws, is this tract or parcel restricted by any recorded covenant that is contrary to, conflicts with, or prohibits the activity described in this application? Yes No

Applicant, Property, and Project Information

Applicant Name: Jeremiah Smith
Applicant Address: 1107 West Street
Applicant E-mail: jeremiah@allisonramseyarchitect.cc Applicant Phone Number: 423-290-1179

Applicant Title: Homeowner Tenant Architect Engineer Developer

Owner (if other than the Applicant): Cara May Cottage, LLC

Owner Address:

Project Name: Cara May Cottage

Property Address: 804 Harrington St & Crofut Ln

Property Identification Number (Tax Map & Parcel Number): R120 004 000 359A0000

Date Submitted: 9-9-2020

Certification of Correctness: I/we certify that the information in this application is correct.

Applicant's Signature: [Signature] Date:
Owner's Signature: [Signature] Date: 9-15-2020

(The owner's signature is required if the applicant is not the owner.)

Required Project Information

See Section 9.10 of the Beaufort Code for complete information about Certificates of Appropriateness and Section 10.7 for complete information about the Historic Review Board | This form is also available online at www.cityofbeaufort.org | updated February 5, 2019

Meredith Jacobs

From: Jeremiah Smith <jeremiah@allisonramseyarchitect.com>
Sent: Wednesday, September 23, 2020 1:48 AM
To: Meredith Jacobs
Cc: Dan Frazier; Heather Spade; David Prichard; Julie Bachety; Jeremy Tate
Subject: RE: 804 Harrington - October HRB - Missing Items
Attachments: Cara May Cottage II 9-22-2020.pdf; HRB -Application - Cara May Cottage 9-15-20.pdf; Images - Site & Context 9-22-20.pdf; Quoizel WVR8406EK Westover 1 Light 17 inch Earth Black Outdoor Wall Lantern.pdf; Window specs.pdf; GAF Timberline Natural Shadow 33.3-sq ft Slate Laminated Architectural Roof Shingles in the Roof Shingles department at Lowes.com.pdf

Meredith,

Thank you for the email and list of missing items. I have attached a complete submission and responded to each item below **in red**. Please let me know if anything else is needed.

Thank you,
Jeremiah

Jeremiah W. A. Smith, Architect

Allison Ramsey Architects, Inc.

1003 Charles Street

Beaufort, SC 29902

Phone: 843-986-0559 Ext: 4

Email: jeremiah@allisonramseyarchitect.com



From: Meredith Jacobs <meredith@meadorsinc.com>

Sent: Friday, September 18, 2020 3:08 PM

To: Jeremiah Smith <jeremiah@allisonramseyarchitect.com>

Cc: Dan Frazier <dfrazier@cityofbeaufort.org>; Heather Spade <hspade@cityofbeaufort.org>; David Prichard <dprichard@cityofbeaufort.org>; Julie Bachety <jbachety@cityofbeaufort.org>; Jeremy Tate <jeremy@meadorsinc.com>

Subject: 804 Harrington - October HRB - Missing Items

Hi Jeremiah,

Thank you for making application to the Historic Review Board. This email confirms receipt of your HRB Application for New Construction of a single family home at 804 Harrington Street.

Upon initial review of your application, we have found that the following items are missing and are required in order for this application to be reviewed at the October meeting. If any of these items are not applicable to your project, please provide a statement that they are not applicable. Please revise your application to include the following and **resubmit a new, complete application** by end of day on **Wednesday, September 23**. Please note that any additional information submitted after this date will NOT be reviewed for the October HRB meeting. If you are unable to meet this deadline, this application will be automatically moved to the November meeting. Please also note that scheduled dates of reviewed applications are subject to the number of applications received.

Missing Items for 804 Harrington Street:

Conceptual:

1. Please update site plan to include any proposed mechanical equipment and associated screening and percentage of total impervious paving. Please also add a hatch to show extent of gravel in rear of structure. **Mechanical equipment is shown and now labeled. No screening is proposed as it is located at the rear. There is no impervious paving proposed. The percentage of impervious on the lot is 47%. A gravel hatch is now shown for the (1) parking pad (10' x 18').**
2. Please include a street elevation or street section that shows height and width relationships to existing adjacent buildings. **Please see Sheet S for Harrington Streetscape from Duke to Washington.**
3. Please label addresses on Harrington Street Context images and tie back to the context map page for clarity. **Addresses have been added to the images. The 4 closest buildings have been labeled on the satellite image.**

Preliminary:

1. Missing Items for Conceptual review noted above. **See above.**
2. Please include ridge heights on elevations. **Note has been added – 19'-5"**
3. Please include a colored version of at least one elevation, noting proposed materials and colors. **Please see cover sheet for elevation with proposed colors. Materials are noted on elevations.**

Final Review:

1. Missing Items for Conceptual and Preliminary Review noted above. **See above.**
2. Please include a section detail through the porch stair. **Please see Sheet 2 for added detail.**
3. Please ensure all paint numbers and names are complete and included on final materials list. **Please see cover sheet.**
4. Please provide cut sheets for all light fixtures, materials, doors and windows, roof shingles. **Spec sheets are attached for front porch light fixture, windows, and roof shingles.**

Thank you,

Meredith Jacobs

Meadors Architecture

2811 Azalea Drive

Charleston, SC 29405


Cell: 843.729.0172

Office: 843.723.8585

www.meadorsinc.com

810 HARRINGTON

811 HARRINGTON



800 HARRINGTON

803 HARRINGTON



CONTEXT



SITE - HARRINGTON ST. & CROFUT LN.

908 HARRINGTON



810 HARRINGTON



910 HARRINGTON
HARRINGTON STREET CONTEXT



1301 WASHINGTON

803 HARRINGTON



1215 PRINCE




811 HARRINGTON
HARRINGTON STREET CONTEXT




800 HARRINGTON

SYMBOLS + KEYS

DOOR AND WINDOW SIZE KEY
2860 = 2'-8" WIDE x 6'-0" HIGH



1 DRAWING TITLE



⚡	SINGLE POLE SWITCH
⚡	THREE WAY SWITCH
⚡	FOUR WAY SWITCH
⚡	DIMMER SWITCH
⚡	SPEED CONTROL
⚡	DUPLEX OUTLET
⚡	1/2 HOT OUTLET
⚡	WATER PROOF OUTLET
⚡	GROUND FAULT OUTLET
⚡	QUADRUPLUX OUTLET
⚡	SPECIALTY OUTLET
⚡	FLOOR OUTLET
⚡	TELEPHONE JACK
⚡	THERMOSTAT
⚡	TELEVISION JACK
⚡	VENT
⚡	VENT w/ LIGHT
⚡	SURFACE MOUNTED FIXTURE
⚡	RECESSED FIXTURE
⚡	WALL MOUNTED FIXTURE
⚡	FLOOD LIGHT
⚡	FLUORESCENT FIXTURE
⚡	CEILING FAN
⚡	STRIP LIGHTING
⚡	CEILING BOX
⚡	DOOR CHIME
⚡	ELECTRICAL PANEL
⚡	SMOKE DETECTOR
⚡	CARBON MONOXIDE DETECTOR

COLORS + MATERIALS LIST - VERIFY w/ ARCHITECT

SIDING / BODY	WHITE - SW7077
WINDOW + DOOR TRIM	WHITE - SW7077
COLUMNS + CORNER TRIM	WHITE - SW7077
STUCCO BASE + BAND BOARDS	FASHION GRAY - COLOR MATCH WINDOWS
EAVES + FASCIA	WHITE - SW7077
TOP RAIL + DIAMOND TRIM	FASHION GRAY - COLOR MATCH WINDOWS
FRONT DOOR	FASHION GRAY - COLOR MATCH WINDOWS; 3/4 GLASS 4 LITE
WINDOWS	FASHION GRAY - SIERRA PACIFIC; 4 LITE CASEMENT
ARCH. SHINGLES	"SLATE GRAY" - GAF TIMBERLINE



CONCEPTUAL RENDERING

DRAWING INDEX

- 0 COVER SHEET
- 5 SITE PLAN/ DRAINAGE PLAN
- 1 FOUNDATION PLAN/
FLOOR PLAN/ ROOF PLAN/
ELECTRICAL LAYOUT/ DETAILS
- 2 ELEVATIONS/ DETAILS
- SP1 SPECIFICATIONS
- SP2 SPECIFICATIONS
- SP3 SPECIFICATIONS

GENERAL INFO.

AREA CALCULATIONS
TOTAL HEATED = 400 S.F.
COVERED PORCH = 46 S.F.

CARA MAY COTTAGE

HARRINGTON STREET + CROFUT LANE, CITY OF BEAUFORT, SOUTH CAROLINA





**CARA MAY
COTTAGE**
HARRINGTON STREET + CROFUT LANE,
CITY OF BEAUFORT, SOUTH CAROLINA

ALLISON RAMSEY
Architects, Inc. creating sustainable timeless design
1003 Charles St.
Beaufort SC 29902
(843) 986-0559
www.allisonramseyarchitect.com

THIS PLAN AND ALL RELATED DOCUMENTS ARE THE PROPERTY OF ALLISON RAMSEY ARCHITECTS, INC. AND ARE TO BE USED ONLY FOR THE PROJECT AND SITE SPECIFICALLY IDENTIFIED HEREIN. ANY REUSE OR REPRODUCTION OF THIS PLAN FOR ANY OTHER PROJECT WITHOUT THE WRITTEN PERMISSION OF ALLISON RAMSEY ARCHITECTS, INC. IS STRICTLY PROHIBITED. THE ARCHITECT ASSUMES NO LIABILITY FOR CONSTRUCTION DEFECTS OR OMISSIONS. THE ARCHITECT'S RESPONSIBILITY IS LIMITED TO THE DESIGN AND CONSTRUCTION OF THE PROJECT AS SHOWN ON THESE PLANS. THE ARCHITECT DOES NOT WARRANT THE ACCURACY OF ANY INFORMATION PROVIDED BY OTHER PROFESSIONALS OR VENDORS. THE ARCHITECT'S LIABILITY IS LIMITED TO THE DESIGN AND CONSTRUCTION OF THE PROJECT AS SHOWN ON THESE PLANS. THE ARCHITECT DOES NOT WARRANT THE ACCURACY OF ANY INFORMATION PROVIDED BY OTHER PROFESSIONALS OR VENDORS. THE ARCHITECT'S LIABILITY IS LIMITED TO THE DESIGN AND CONSTRUCTION OF THE PROJECT AS SHOWN ON THESE PLANS. THE ARCHITECT DOES NOT WARRANT THE ACCURACY OF ANY INFORMATION PROVIDED BY OTHER PROFESSIONALS OR VENDORS.

DATE:	09/09/2020
JOB NO.:	19912
DRAWN BY:	JMS
DWG. NAME:	19912.DWG

0




**CARA MAY
COTTAGE**
HARRINGTON STREET + CROFUT LANE,
CITY OF BEAUFORT, SOUTH CAROLINA


ALLISON RAMSEY
Architects, Inc. creating sustainable timeless design
1003 Charles St.
Beaufort SC, 29902
(843) 786-0359
www.allisonramseyarchitect.com

THIS PLAN IS TO BE USED TO OBTAIN PERMITS AND TO BE USED FOR CONSTRUCTION. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO VERIFY THE LOCATION OF ALL UTILITIES PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS FROM ALL APPLICABLE AGENCIES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS FROM ALL APPLICABLE AGENCIES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS FROM ALL APPLICABLE AGENCIES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS FROM ALL APPLICABLE AGENCIES.


DATE:	09/22/2020
JOB NO.:	19912
DRAWN BY:	JMS
DATE:	1992/01/01




Copyright 2020 by Allison Ramsey Architects, Inc. All rights reserved.




7 EXTERIOR LIGHTING MOUNT DETAIL
SCALE: 1 1/2" = 1'-0"




4 CONTROL JOINT DETAIL
SCALE: 3/4" = 1'-0"




3 THICKENED SLAB DETAIL
NOT TO SCALE



5 6x6 POST DETAIL
SCALE: 3/4" = 1'-0"




6 PICKET & RAIL DETAIL
SCALE: 1 1/2" = 1'-0"




ROOF PLAN
SCALE: 1/8" = 1'-0"


NOTE: EXHAUST VENTS (PLUMBING OR OTHERWISE) NEED TO BE LOCATED AS INCONSPICUOUS AS POSSIBLE. ROOF PENETRATIONS NEED TO BE KEPT TO A MINIMUM (COMBINED WHEN POSSIBLE). ROOF / WALL PENETRATIONS MUST BE PAINTED TO MATCH SURROUNDING COLOR.




2 TYPICAL PORCH SECTION
SCALE: 3/4" = 1'-0"




1 TYPICAL WALL SECTION
SCALE: 3/4" = 1'-0"



ELECTRICAL PLAN
SCALE: 1/4" = 1'-0"



FIRST FLOOR PLAN
SCALE: 1/4" = 1'-0"



FOUNDATION PLAN
SCALE: 1/4" = 1'-0"

NOTE: CONTROL JOINTS + THICKENED SLAB TO BE PLACED PER RC OR STRUCTURAL.

CARA MAY COTTAGE
HARRINGTON STREET + GROFUT LANE,
CITY OF BEAUFORT, SOUTH CAROLINA

ALLISON RAMSEY Architects Inc.
creating sustainable timeless design
1003 Charles St.
Beaufort, SC 29902
(843) 986-0359
www.allisonramseyarchitect.com

THIS PLAN IS BEING PROVIDED TO YOU FOR YOUR INFORMATION ONLY. IT IS THE RESPONSIBILITY OF THE ARCHITECT TO PROVIDE THE FOLLOWING INFORMATION TO YOU. ANY INFORMATION NOT ON THIS PLAN IS NOT TO BE USED FOR CONSTRUCTION. ALL INFORMATION ON THIS PLAN IS SUBJECT TO CHANGE WITHOUT NOTICE. ALL INFORMATION ON THIS PLAN IS SUBJECT TO CHANGE WITHOUT NOTICE. ALL INFORMATION ON THIS PLAN IS SUBJECT TO CHANGE WITHOUT NOTICE.

DATE:	09/22/2020
JOB NO.:	19912
DRAWN BY:	JMS
CHECKED BY:	PRZ

Copyright 2020 by Allison Ramsey Architects, Inc. All rights reserved.

Building Supplies / Roofing / Roof Shingles

\$29.00

★★★★★ 488

[View Q&A](#)

BUY 36 GET 20% OFF

GAF Timberline Natural Shadow 33.3-sq ft Slate Laminated Architectural Roof Shingles

Item #652981 Model #0600750

Architectural style that's practically priced

Features a classic shadow effect that lends any home a subtle, even-tone with the warm look of wood in an asphalt shingle


Highest roofing fire rating: UL Class A, Listed to ANSI/UL 790

Manufacturer Color/Finish: Slate

- 1 +

Please Enter Minimum Qty of 3

Add to Cart

**Free Store Pickup**182 Available at [Beaufort Lowe's](#) Aisle 53 | Bay 9**Delivery**

Available

Overview

Your roof can represent up to 40% of your home's curb appeal. Improve its resale value with Timberline® natural shadow® Shingles from GAF. Installing the rugged, dependable performance of Timberline® natural shadow® Shingles will give you the upscale, architectural look you want at a price you can afford.

- Architectural style that's practically priced
- Features a classic shadow effect that lends any home a subtle, even-tone with the warm look of wood in an asphalt shingle
- Highest roofing fire rating: UL Class A, Listed to ANSI/UL 790
- Advanced protection shingle technology reduces the use of natural resources while providing excellent protection for your home
- Dura Grip Adhesive seals each shingle tightly to roof reducing the risk of shingle blow-off; Shingles warranted to withstand winds up to 130 mph
- Wind speed coverage requires special installation; see GAF shingle and accessory limited warranty for complete coverage and restrictions
- Lifetime limited transferable warranty with smart choice protection (non-prorated material and installation labor coverage) for the first ten years; see GAF shingle and accessory limited warranty for complete coverage and restrictions

[Installation Guide](#)
PDF [Warranty Guide](#)
PDF [Operating Guide](#)
PDF [CA Prop 65](#)
PDF

VIP Code: JMLD2KXM14

866-344-3875

Live Chat

Login

My Lists

My Cart



A LIGHTING NEW YORK STORE

Search

Search



Customer Care | Professional Discounts

- Shop by Room
- Shop by Style
- Shop by Category
- Shop by Collection
- Best Sellers
- Sales & Clearance
- Open Box

Questions about delivery times? Call a Lighting Expert now at 866.344.3875

Home » Westover » Outdoor Wall Lights » Quoizel WVR8406EK

Quoizel WVR8406EK

Westover 1 Light 17 inch Earth Black Outdoor Wall Lantern



Call 844.344.3536 For Trade Pricing

\$99.99 PER EACH

COUPON SALE

★★★★☆ of 5 Reviews

100+ IN STOCK

FREE Shipping & Returns

NO Restocking Fee

110% Price Match Guarantee

Enter Coupon **AUTUMN20** in your cart.
Save 10% on Quoizel, now through 09/30/20 11:59 PM et.

[View Terms and Conditions](#)

Original List Price: ~~\$150.00~~ (You Save 33.00%)

Finish
Earth Black

1

Add To Shopping Cart

Add to List

Price Alert

Make an Offer

[Return Policy](#)

[Shipping Policy](#)

[110% Price Match](#)



Zoom Image



- Product Information
- General Information
- Manufacturer's Catalog(s)
- Questions

General Information

Quoizel WVR8406EK
Westover 1 Light 17 inch Earth Black Outdoor Wall Lantern

The clean lines and hand-riveted accents make the Westover a modern industrialist's dream. Long rectangular framework with clear glass panels provide an unobstructed view of the lantern's sleek interior. The earth black finish further enhances the versatility of this refined collection.

Brand Information

- Brand: Quoizel
- Collection: Westover
- SKU: WVR8406EK

Design Information

- Category: Outdoor Wall Lights
- Finish: Earth Black
- Glass: Clear With Beveled Edge

VIP Code: JMLD2KXM14

866-344-3875

Live Chat

Login

My Lists

My Cart

Dimensions and Weight

- Length: 7.50 in.
- Width: 6.00 in.
- Height: 17.00 in.
- Backplate/Canopy Width: 4.50 in.
- Backplate/Canopy Length: 7.00 in.
- Weight: 8.71 lb.

Other Specifications

- Ships Via: Ground (FREE SHIPPING)
- Included Suspension: 6 In Cord
- Warranty: Limited Warranty

Additional Details

- Limited Warranty Electrical Components 10 Years, Finish - Indoor & Outdoor 3 Years, Coastal Armour - Outdoor Finish 5 Years

Bulb Information

- Bulbs Included: No
- Primary Bulb(s): 1 x 100.00 watts Medium A19

Product Rating

- Voltage: 120V
- Safety Rating: ETL Listed

Documents

- Install Sheet: IS-WVR8406EK.pdf



autumn VIBES

save 10% OFF the entire line with code: AUTUMN20

SAVE NOW >>



QUOIZEL LIGHTING

MAKE AN ENTRANCE

SHOP NOW >>

1 2

Quoizel's Catalogs



Customer Reviews



Product Questions

Questions about Quoizel WVR8406EK

Ask us a question...

Be the first to ask a question about this product!

Every Order Includes

No Restocking Fees!

Quick Ship In stock items ship in 1-2 business days.

Free Shipping On all items able to be sent in the contiguous United States.

International Shipping Now available! Call 866.344.3875 for more information.

Free Returns Within 30 days of purchase for like new, uninstalled items.

110% Price Match Find a lower price and we'll beat it by 10% of the difference.

Lighting New York Business Hours

Lighting Experts Mon - Fri 8am to 12am EST Sat & Sun 9am to 12am EST

Customer Care Mon - Fri 8am to 6pm EST

Shop Now

- Shop Rooms
- Shop Styles
- Shop Categories
- Shop Collections
- Shop Best Sellers
- Shop Sales

Customer Care

- Contact Us
- Shipping
- Ordering Info
- Guarantee
- Privacy Policy
- California Privacy Disclosures
- Accessibility Policy

My Account

- Log In (Sign Up)
- My Orders
- My Lists
- My Addresses
- My Product Reviews
- Log Out

Payment Accepted



Feel Secure Shopping at Quoizel Lighting Lights



QUOTATION

ESPY LUMBER COMPANY
 3785 Argent Blvd.
 Okatie, SC
 (843) 379-5000



BILL TO:
 Jeremiah Smith

SHIP TO:
 Casa May Cottage
 Harrington St.
 Beaufort, SC

Phone
 Email

Phone
 Fax

QUOTE #	PO #	QUOTE NAME	PROJECT	JOB NAME	CUSTOMER PO #
1175718		Jeremiah Smith - Allison Ramsey Arch	Cara May Cottage	Smith	

LINE #	LINE TYPE	DESCRIPTION	QTY	U/M	NET PRICE	EXTENDED
100-1	WindowAndDoor	PK- 330	2	EA	\$664.54	\$1,329.09

****2020 PRICING****

H3 Aluminum Clad Casement Windows 2.0 Casement Right 29.5 x 77.5
 30 x 78, Frame Width = 29.5, Frame Height = 77.5, Screen Width = 26.125, Screen Height = 73.15625

Complete Unit, CoreGuard Plus

Frame Color = Battleship Gray 321, AAMA 2604, Primed Interior, Interior Primed Finish = White, Pine Interior, Frame Jamb Style = Flush

Sash Color = Battleship Gray 321, AAMA 2604, Sash Interior = Primed Interior, White

Dual Insulated, Low-E 366, Argon Gas, Black Warm Edge Spacer

Hardware = Shipped with Unit, E-Guard Finish (Beige), Encore, White, WOCD=No, 14" Hinge

Full Screen Shipped Separately, White, Fiberglass Mesh

Simulated Divided Lite, Equal, Grille Profile = Putty, 7/8", Interior Bar Height = .260, Exterior Color = Battleship Gray 321, 2604, Primed Interior, Interior Grille Primed Color = White, Pine Interior, w/spacer, Dark Bronze Anodized, 2W2H, Grille Type Custom

Integral Rigid Vinyl Nailing Fin, No Drip Cap


6 9/16" 1-Piece, Match Interior Wood = Yes, Pine Jamb Extension, Primed Interior, Jamb Extension Primed Color = White, Entire Set

U-Factor = 0.28, SHGC = 0.19, CR = 60, VT = 0.42, AI = <0.30/<1.5, CPD =

SIE-N-136-01139-00004, Energy Star Region = NC,SC,S, GapFill1 = ARG, Can ER = 16, W m 2k = 1.59

PG50, FBC = FL20064.3, TDI = WIN-2244

Unit 1: Glass Width = 25.5, Glass Height = 73.5, Sash Width = 27.75, Sash Height = 75.75



Rough Opening: 30" X 78"

Overall Unit Size: 29.5" X 77.5"

Room Location: Living



Historic Review Board Meeting Staff Report

From the Department of Community and Economic Development
14 October 2020

1 SUMMARY OF REQUEST

804 Harrington Street, New Construction

Applicant: Jeremiah Smith (20-42 HRB.1)

The applicant is requesting final approval for new construction of single-family dwelling at 804 Harrington Street.

This is an existing and vacant non-conforming lot within the Historic Conservation Neighborhood and the Northwest Quadrant.

2 FACTS

Property Address:	804 Harrington Street
Parcel ID:	R120 004 000 359A 0000
Case Number:	20-42 HRB.1
Applicant:	Jeremiah Smith
Zoning:	T4-HN
Use:	Single Family Dwelling



District Development Standards for T4-HN:

- **Setback requirements –**
 - *Front: Average prevailing setback on block.*
 - *Rear setback – 15' min.*
 - *Side Corner/Alley – 5' min. – no max.*
 - *Side Interior – 6' min.*
- **Primary Building Height:** 3 stories, max.
- **Parking Pad Location:**
 - Front: 40 ft. min.
 - Side Setback – Corner: 5' min.
 - Rear Setback: 5 ft. min.
- **Impervious Surface Coverage:** 55% maximum
- **Frontage Buildout:** 75% maximum
- **Permitted Uses:** Single Family dwelling, or Two- or Three-Unit Dwelling is permitted by right in the T4-HN zoning classification.

Historical Background:

The property is a non-conforming lot located within the Historical Conservation Neighborhood. The parcel was lawfully created prior to the adoption of the Beaufort Code.

The parcel is considered a nonconforming lot because it does not meet the dimensional requirements of the code for minimum lot size in the T4-HN zone, which is 4,000 square feet. The parcel is only 946.1 square feet.

Although it does not meet the dimensional requirements for T4-HN, it is considered a buildable lot provided that “the property can be developed as proposed without any significant adverse impact on surrounding properties or the public health or safety” (see p. 225, The Beaufort Code, 11.5.2.B.3 Nonconforming Lots of Record).

The Beaufort County Assessors data shows no history of a structure located on the parcel.

The applicant previously applied for a two-story single-family dwelling on this property. This application received final approval with changes discussed on February 12, 2020.

References:

- The Beaufort Code, Specifically Chapters 2, 3, 4, 5, and 11.
- The Beaufort Preservation Manual and Supplement
- Northwest Quadrant Design Principles, Specifically Chapters 2 and 3

3 STAFF COMMENTS/ RECOMMENDATIONS

1. Deviations from the setback requirements are permitted for nonconforming lots of record per Section 11.5.2 Standards for Development of the Beaufort Code (p.225). The following deviations from the established minimum T4-HN setbacks were approved during the previous application submission for this project, and this new proposed application still complies with these setbacks:
 - a. Front: 1’
 - b. Side, alley: 1’
 - c. Side, interior: 1’

The rear of the building is 16’ from the property line, which is compliant with the established minimum rear T4-HN setback of 15’ of the Beaufort Code.

2. Per Section 5.7.4 Parking Space Requirements of the Beaufort Code (p.126), two parking spaces are required for each single-family residential unit. The proposed project provides for only one parking space. However, Section 5.7.6.C Parking Reductions (p.128), allows for administrative approval of a reduction in parking when an applicant can demonstrate that the reduction is warranted. The applicant has requested a reduction in parking and has demonstrated that the reduction is warranted.
3. The proposed project meets the Tree Coverage Requirement for the zone and lot size as per code which is one (1) over-story tree per 4,000SF as per Section 5.3 Tree Planting and Protection of the Beaufort Code. The site is one-quarter (1/4) the min. lot size, but an existing 8” Laurel Oak will satisfy the tree coverage requirement without planting additional trees. (pp. 115-116, Article 5 Landscaping, Parking & Lighting of the Beaufort Code).


4. The proposed building meets the requirements of Chapter 4 of the Beaufort Code regarding building materials and details, roof forms, windows, and architectural details such as column bays. No cut sheet was provided for the exterior door. Per Section 4.6.3.A.5 of the Beaufort Code, this door shall be made of wood, metal, glass, or fiberglass. Please note that, per Section 4.6.3.A.8, fiberglass may only be permitted on a context specific basis, at the discretion of the Design Review Body.
5. The proposed new construction appropriately responds to the following Northwest Quadrant Design Principles applicable for new construction:
 - a. **Maintain the informal nature of streets, lanes, and gardens where they exist.** Crofut Lane provides access to the rear gravel parking area and can be maintained in an informal manner as a grassy lane (page 19).
 - b. **Maintain the traditional character of a front yard.** The new design creates more space for a “front yard” beside the porch and in front of the bay window.
 - c. **Building forms should be like those seen traditionally.** The gabled porch front and rectangular form of the proposed building form appropriately responds to the Northwest Quadrant Design Principles with respect to its similarity to building forms traditionally found in the Northwest Quadrant.
 - d. **Building should appear similar in scale of houses found traditionally in the neighborhood.** Most houses in the Northwest Quadrant are one-story cottages with a front porch or entry element, which is what is proposed for 804 Harrington Street.
 - e. **Building Materials should be like those used traditionally in the neighborhood.** Page 31 (11.4) of the Northwest Quadrant Design Principles notes that “new materials that are similar in character to traditional materials are acceptable for...new construction.” The proposed use of Fiber Cement siding is therefore acceptable on this structure. Applicant to note that, per section 4.6.3.A.1.b of the Beaufort Code, Fiber Cement siding is to be smooth.

STAFF RECOMMENDATION:

Final Approval, pending review of the front door cut sheet.

CITY STAFF INTRODUCTION

1711 KING STREET



PROJECT LOCATION -1711 KING STREET



©2020 J. ROBERTS



37110

SCDOT

FL



HISTORIC SITES SURVEY - 1997

RECONNAISSANCE LEVEL BUILDING INVENTORY FORM

Statewide Survey Site Form
State Historic Preservation Office
South Carolina Department of Archives and History
Columbia, SC

Site Number: U- 13 - 1263
Access County Site #

USGS Quad: 025 Beaufort
Doc. Level: Reconnaissance Level

Historic name(s): _____ Map Ref.: BET.08 Tax Number: R12000300002240000
Common name(s): _____ City Block Ref.: 137 Island: Port Royal Is.
Address/location: 1711 King St. City/Vicinity of (vic.): Beaufort
Date: 1920 Alteration date: ca. 1945
Ownership: 1. private 2. city 3. county 4. state 5. federal 6. unknown
Category: 1. building 2. site 3. structure 4. object
Historic use(s): single dwelling Current uses: single dwelling
Notes: Rectangular 2 story 4 x 2 bay frame dwelling w/hipped roof

National Register Status: _____ Date: _____ Listing Name: _____ NRIS # _____
National Register Historic District (NHL, 11/73) 12/17/69 Beaufort Historic District 69000159

SHPO National Register Evaluation: Contributes to listed district Name: Beaufort Historic District

Consultant Recommendation: _____ Name: _____

Previous Survey: _____ Reference: _____ Notes: _____
 H.A.B.S. Other _____
 Feiss-Wright (1969) _____
 Historic Resources of the Lowcountry (1979) _____
 Milner Historic District Inventory (1979) _____
 A Guide to Historic Beaufort (1995 ed.) _____

Photograph:



Photographs:

- prints
- slides
- negatives

Date: 8/1/97

Recorder: D. Schneider, Historic Beaufort Fdn.

Roll # Neg. View of:
S-14 26 S facade & W elev., fac. NE

**BEAUFORT COUNTY HISTORIC SITES INVENTORY
 SITE INDEX**




P O Box 11
 Beaufort, SC 29902
 (803) 524-6334

Community: Northwest Quadrant
 Address: 1711 King St.

HBF Site #-	195
NW Quad -	5

Historic Name:
 Designated: NHL district - contributing Status: Contributing Integrity: good
 Year Built: circa 1920 Significance: 3 contributes to area
 Historic Use: single dwelling Current Use: single dwelling Condition: excellent
 Stylistic Period: Colonial Revival Sub Style: vernacular
 Desc.: Two story 4 x 2 bay block w/additions; 1 story hipped porch at facade w/1 bay roofed balcony, supports on pedestals & ballustrade at balcony
 Sign.:
 Notes:
 Neg#: 96.01.08 Add. Neg.: Block #: 134 Faces: 3. South
 Contact:
 Date Surveyed: 2/12/96 By: D. Schneider, Historic Date Modified: 4/21/96
 Quad: Beaufort East: North: TMS#



**BEAUFORT COUNTY HISTORIC SITES INVENTORY
 SITE INDEX**



P O Box 11
 Beaufort, SC 29902
 (803) 524-6334

Community: Northwest Quadrant
 Address: 1705 King St.

HBF Site #-	196
NW Quad -	6

Historic Name:
 Designated: NHL district - contributing Status: Contributing Integrity: good
 Year Built: circa 1900 Significance: 3 contributes to area
 Historic Use: single dwelling Current Use: single dwelling Condition: good
 Stylistic Period: hall & parlor Sub Style: folk type
 Desc.: 5 x 1 bay rectangular block; 2 gable dormers; 9/9 light sash; wooden shutters
 Sign.: needs research, is it as old as style indicates
 Notes:
 Neg#: 96.01.09 Add. Neg.: Block #: 134 Faces: 3. South
 Contact:
 Date Surveyed: 2/12/96 By: D. Schneider, Historic Date Modified: 4/21/96
 Quad: Beaufort East: North: TMS#



APPLICANT PRESENTATION

1711 KING STREET

New Roof Replacement request/Historic District/Beaufort SC

Please find the included attachments:

3 page required paperwork application

3 color photos of house (current)

Letter from professional roofer explaining where/why the roof is now failing

Estimate from roofing company explaining what materials will be used on new roof

3 color photos – existing homes in proximity of 1711 King already using asphalt shingles

Verification of payment of \$100.00 for application fee

Thank you for your effort in this matter.

If there is anything that is missing or you question please contact me as soon as possible as addressing this issue is of utmost importance.

Lorraine Yaralian

1711 King Street 29902

Blurbit@aol.com 719.588.5489

Will be submitted to:

hspade@cityofbeaufort.org

meredith@meadorsinc.com

jbachety@cityofbeaufort.org

jeremy@meadorsinc.com

dfrazier@cityofbeaufort.org



DEVELOPMENT REVIEW PROCESS
HISTORIC REVIEW BOARD APPLICATION

Community & Economic Development Department
1911 Boundary Street, Beaufort, South Carolina, 29902
p. (843) 525-7011 / f. (843) 986-5606
www.cityofbeaufort.org

- Staff Review
Board Review

Application Fee:
see attached schedule

OFFICE USE ONLY: Date Filed: Application #: Zoning District:
BCAGHS Survey: Yes No

Schedule: The Historic Review Board (HRB) typically meets the 2nd Wednesday of each month at 2pm. The complete schedule, along with the list of deadlines, may be found here - http://www.cityofbeaufort.org/historic-review-board.aspx

Submittal Requirements: All forms and information shall be submitted digitally. In addition to a complete application form, applicants shall submit the required items according to the checklists on the subsequent page.

Review Request: Conceptual Preliminary Final Bailey Bill Approval* Change After Certification
*Requires a Bailey Bill - Part A Preliminary Review Application Form

Pursuant to Section 6-29-1145 of the South Carolina Code of Laws, is this tract or parcel restricted by any recorded covenant that is contrary to, conflicts with, or prohibits the activity described in this application? Yes No

Applicant, Property, and Project Information

Applicant Name: Lorraine Yaralian

Applicant Address: 1711 King Street

Applicant E-mail: Blurbit@aol.com Applicant Phone Number: 719.588.5489

Applicant Title: Homeowner Tenant Architect Engineer Developer

Owner (if other than the Applicant): Blake Yaralian (Son)

Owner Address: 90 Tower Hill Road Mtn Lakes NJ 07046

Project Name: New Roof Request

Property Address: 1711 King Street Beaufort SC 29902

Property Identification Number (Tax Map & Parcel Number): R120 003 000 0224 0000

Date Submitted: 8/26/2020

Certification of Correctness: I/we certify that the information in this application is correct.

Applicant's Signature: Lorraine Yaralian Date: 8/25/2020

Owner's Signature: Blake Yaralian Date: 8/25/2020

(The owner's signature is required if the applicant is not the owner.)

Required Project Information

See Section 9.10 of the Beaufort Code for complete information about Certificates of Appropriateness and Section 10.7 for complete information about the Historic Review Board | This form is also available online at www.cityofbeaufort.org | updated February 5, 2019



**DEVELOPMENT REVIEW PROCESS
HISTORIC REVIEW BOARD APPLICATION**

Community & Economic Development Department
1911 Boundary Street, Beaufort, South Carolina, 29902
p. (843) 525-7011 / f. (843) 986-5606
www.cityofbeaufort.org

Project Name: New Roof Request

Property Size in Acres: _____ Proposed Building Use: _____

Nature of Work (check all that apply):

- New Construction, Primary Structure
 New Construction, Primary Structure
 Alterations / Additions
 Demolition*
 Relocation*
**Demolition and Relocation requires a public hearing*

Building Square Footage (if multiple buildings, please list each one and their square footage by floor):

Is this project a redevelopment project? Y N

Are there existing buildings on the site? Y N if yes, will they remain? Y N

Provide a brief Project Narrative (if requesting Bailey Bill Approval, this section may be left blank):

Requesting permission to replace failed metal roof with an asphalt shingle roof at 1711 King Street.

Pls find attachments - older homes in immediate area - Shingle roof

We are seeking permission to replace a failed metal roof with an Asphalt Shingle Roof. The difference in price metal vs shingle is the breaking point in our decision as to which roof to choose.

Metal is twice the price as the Asphalt Shingle roof. With the financial difficulties we are all facing today we are hopeful you will grant us permission to use Asphalt Shingles on the roof of 1711 King Street. Beaufort SC 29902.

We believe this type of roof will not distract from the historical flavor of King Street since they already exist. Thank you, Yaralians

We are thinking of choosing a red/brick color asphalt shingle

CONTACT INFORMATION -

Attention: Julie A. Bachety, Administrative Assistant II

City of Beaufort Department of Planning & Development Services

1911 Boundary Street, Beaufort, South Carolina 29902

E-Mail: jbachety@cityofbeaufort.org | Phone: (843) 525-7011 | Fax: (843) 986-5606

See Section 9.10 of the Beaufort Code for complete information about Certificates of Appropriateness and Section 9.7 for complete information about the Historic Review Board. This form is also available online at www.cityofbeaufort.org | updated February

HISTORIC SITES SURVEY - 1997

RECONNAISSANCE LEVEL BUILDING INVENTORY FORM

Statewide Survey Site Form
State Historic Preservation Office
South Carolina Department of Archives and History
Columbia, SC

Site Number: U- 13 - 1263
Access County Site #

USGS Quad: 025 Beaufort
Doc. Level: Reconnaissance Level

Historic name(s): _____ Map Ref.: BET.08 Tax Number: R12000300002240000
Common name(s): _____ City Block Ref.: 137 Island: Port Royal Is.
Address/location: 1711 King St. City/Vicinity of (vic.): Beaufort
Date: 1920 Alteration date: ca. 1945
Ownership: 1. private 2. city 3. county 4. state 5. federal 6. unknown
Category: 1. building 2. site 3. structure 4. object
Historic use(s): single dwelling Current uses: single dwelling
Notes: Rectangular 2 story 4 x 2 bay frame dwelling w/hipped roof

National Register Status: _____ Date: _____ Listing Name: _____ NRIS # _____
National Register Historic District (NHL, 11/73) 12/17/69 Beaufort Historic District 69000159

SHPO National Register Evaluation: Contributes to listed district Name: Beaufort Historic District

Consultant Recommendation: _____ Name: _____

Previous Survey: _____ Reference: _____ Notes: _____
 H.A.B.S. Other _____
 Feiss-Wright (1969) _____
 Historic Resources of the Lowcountry (1979) _____
 Milner Historic District Inventory (1979) _____
 A Guide to Historic Beaufort (1995 ed.) _____

Photograph:



Photographs:

- prints
- slides
- negatives

Date: 8/1/97

Recorder: D. Schneider, Historic Beaufort Fdn.

Roll # Neg. View of:
S-14 26 S facade & W elev., fac. NE



©2020 J. ROBERTS







877-676-6373

www.roof-crafters.com

20 Towne Dr. ste #208, Bluffton, SC 29910

Mrs. Yaralian,

Thank you for inviting me to your beautiful home. It was a pleasure meeting with you. After a full and thorough inspection of your roof it is in my professional opinion that the following actions be taken.

You must replace the existing roof as soon as possible to prevent any damage to the interior of your home. After inspecting the condition of your metal roof, it is in my professional opinion that there is nothing you can do to repair the panels. There is too much rust and in most cases the panels are so brittle they will fall apart if too much weight or pressure is put on them. The roof decking in some areas will need to be replaced. This is due to the overall deterioration of the metal panels that is causing the decking to rot. There are also holes and cracks in the metal roof causing damage every day that goes by and will continue until you are able to replace the roof. You are running a high risk of interior water damage if the roof is not addressed quickly. Also, in some areas the rust is so bad that if someone walked on them and didn't realize where or what they were walking on they could severely injure themselves by falling through the panels. I hate being the bearer of bad news but at least you know the extent of damage that you have. The good news is we have a solution to fix it. If you have any questions, feel free to call me at any time. I look forward to working with you and your husband.

Sincere thanks,

Anthony Marzbanian

ROOFCRAFTERS

Lead Estimator

(c)843-505-2356

(o)877-676-6373

We CAN because WE C.A.R.E.



14 Savannah Highway Suite 23,
Beaufort, South Carolina, 29906
843-298-6012 or 842-295-0491 Office
Two_Brothers_Roofing@hotmail.com

PROPOSAL SUBMITTED TO	PHONE	DATE	
Madine O'Quinn	(843) 473-9020	08/26/2020	
ADDRESS	JOB NAME		
1711 King Street	2008-1604783-01		
CITY	STATE	ZIP	JOB LOCATION
Beaufort	South Carolina	29902	1711 King Street

GAF ROOFING SYSTEM + METAL ROOF ON THE FRONT AND BACK LOW SLOPES

- 1) Removal of the asphalt shingles
 - Existing roof will be removed to a clean deck to prepare for a new install (1 layer include)
 - Double axle dump trailer to haul off debris
- 2) GAF Feltbuster Synthetic Underlayment
 - Install over the entire roof
- 3) GAF Weatherwatch Ice and Water Shield
 - Install in the valleys, around pipe boots and flashing
- 4) Drip Edge - Wide
 - Install over the entire perimeter of the house
- 5) GAF Pro Start- Starter shingle
 - Install over the entire perimeter of the house
- 6) GAF Timberline HDZ Shingles
 - High Definition Shingle with Unlimited Wind Zone Protection
- 7) Install Shingles with 6 roofing nails per shingle
- 8) GAF Cobra Ridge Vent
 - Install on all the ridges of the house
- 9) GAF Seal-A-Ridge - Install on all ridges and hips
- 10) Pipe Boots - 3 in 1 pipe boot
- 11) Plywood - TBR includes the first 3 sheets of plywood. Any more plywood used on the house will be \$75 more per sheet.
- 12) Roofing MISC Items
 - button caps, roofing nails and caulking
- 13) Any 1x4, 1x6, 1x8, or 2x4, 2x6, or 2x8 that is needed will be charged at an additional charge of \$9 per Lr foot
- 14) TBR will attempt to reuse the existing flashing. If the flashing is not up to SC code or if it is damaged, there will be an additional charge of \$9 per foot added to the total as a change order
- 15) GAF System Plus Warranty- 50 year warranty on the Materials with a 5 year Workmanship Warranty with



RoofCrafters SC and GA
1308 US HWY 80
Bloomington, GA 31302
Phone: 912-920-4147

Company Representative
Anthony Marzbanian
Phone: (843) 505-2356
anthony@roof-crafters.com

Job: Nadine O'Quinn

Nadine O'Quinn
Buy Beaufort Homes
1711 King Street
Beaufort, SC 29902 (843) 473-9020

Shingles Section

Certainteed Landmark Pro architectural shingle with 5-Star warranty

Shingles Section - Color: _____

Drip Edge - Color: _____

SCOPE OF WORK:

- Provide all building permits required by city or county.
- Provide copy of general liability, worker's compensation and state license upon request.
- Provide all set-up, waste disposal measures, safety equipment and manpower needed to complete the project.
- Apply tarps and/or other measures to ensure protection of your landscaping.
- Remove existing shingles and underlayment, to expose existing decking.
- Inspect decking and re-nail any loose wood.
- Replace any damaged or rotted decking found, with like type and thickness. (2 - 4x8 sheets included).
- Install Certainteed WinterGuard ice and water shield at all gutter lines, rake edges, and valleys.
- Install Diamond Deck synthetic underlayment.
- Install new 2-1/2" eave drip flashing, pre-painted, at perimeter of roof, per manufacturer's specifications.
- Install Certainteed SwiftStart starter shingles along all gutter lines and rake edges.
- Install Certainteed Landmark Pro Lifetime Dimensional Shingles per specifications using 1 1/4" roofing nails. (6 nails per shingle)
- Install Certainteed Ridge Vent, per manufacturer's specifications.
- Install Certainteed CedarCrest Ridge hip & ridge shingles, per manufacturer's specifications.
- Install new pipe flashing on all pipes vents.
- Apply sealant on exposed nail heads on all vents and flashings.
- Clean up all job related debris on a daily basis and conduct a thorough cleaning upon completion of the new roof.
- Conduct a final walk-through by a RoofCrafters Field Supervisor to ensure job integrity.
- Order final inspection, as required.
- Crews will maintain safety requirement at all times during the construction process.
- Provide owner with transferable Certainteed 5 STAR WARRANTY: Lifetime shingle warranty (50 years non-prorated) material warranty and 25 year workmanship warranty.

ADDITIONAL ITEMS INCLUDED:

EXCLUDES:


- Gutter work, unless listed above.
- Fascia, soffit or other wood work, unless listed above.
- Interior work, unless listed above.

ADDITIONAL DECKING DISCLAIMER

We do our best to determine the amount of decking that may be needed, during the initial roof inspection. Damage can be hidden by the existing roof surfaces and not observed until that material is removed. RoofCrafters shall provide up to (2) sheets with above quote. Your Field Supervisor will notify you if additional decking is needed and can provide photos showing the damaged wood found. Your final invoice will include the price for any additional decking required and each additional sheet of decking installed, will only be \$85 per sheet.

WEATHER

current asphalt roof



1811 King Street
Beaufort SC
29902

current asphalt roof




1606 King Street
Beaufort SC
29902

Current asphalt roof



1705 King Street
Beaufort SC
29902

This is a "printer friendly" page. Please use the "print" option in your browser to print this screen.



Beaufort, City of, SC
Business License Payment

Confirmation Number

QQ9HZWLL

Date & Time

Tuesday, September 22, 2020 01:11PM ET

Successful completion of the payment transaction is conditioned upon accurate and complete information being entered by you and is subject to financial institution and biller acceptance, approval and authorization of the payment. Electronic check payments may take up to seven business days to be returned by your Financial Institution if incorrect information is entered when a payment is submitted.

Payment Method	Amount	Service Fee	Total
 Ending in ***01	\$100.00	\$1.00	\$101.00

Account Information

Name	lorraine m yaralian
Street Address	1711 king street
City	beaufort
State	SC
Zip code	29902
Country	United States
Daytime phone	(719) 588 - 5489
Email	blurbt@aol.com

Payment approved

September 23, 2020

Addendum to application for roof replacement/ 1711 King
Street/29902

Per two roofing companies a color/colors that I had selected as the
asphalt shingle will not be available due to Covid.


For both the GAF and the Certified I will choose a charcoal/black...
the basic colors that are still available before the end of the year
due to supply chain issues.

That being said the metal portion will still be Terra Cotta (Sheffield
Metals)

Thank you for your attention to this update information.


GAF

Timberline



Charcoal

Certainteed



Charcoal



METAL ROOFING SYSTEMS




SMI 1.0" Mechanical Seam Standing Seam

Panel Information:

Panel Type:	Standing Seam
Panel Seam:	Mechanical
Panel Width:	17"
Seam Height:	1.0"
Panel Material:	22 GA - 24 GA Min
Panel Surface:	Smooth / Embossed Optional
Minimum Slope:	3/12

Panel Notes:

- This panel uses a 20" coil. Maximum width coil of 20".
- This panel uses 3" of material to form the panel.
- If you take the square footage of the roof and multiply that by 1.18, the total will be the amount coil needed to manufacture the panels.
- Suitable for zinc and copper.



CLEVELAND: 800.283.5262
ATLANTA: 800.929.9359
DALLAS: 877.853.4904
DENVER: 877.375.1477
SAN JOSE: 408.916.3262
www.sheffieldmetals.com

9/24/2020

Re: I know your busy!! 1711 Roof Replacement/ridiculous questions from the city of Beaufort.

From: anthony@roof-crafters.com,

To: blurbit@aol.com,

Subject: Re: I know your busy!! 1711 Roof Replacement/ridiculous questions from the city of Beaufort.

Date: Thu, Sep 24, 2020 10:25 am

It would be the Sheffield 1” and do they want pictures of the ridge and hip profiles or do they need samples in hand?

Sincere thanks,

Anthony Marzbanian

ROOFCRAFTERS

Estimator

(c)843-505-2356

(o)877-676-6373

Leave me or my awesome team a review!

Our clients love ROOFCRAFTERS! Review here!



South Carolina-Georgia-Florida

<http://roof-crafters.com/>

On Sep 23, 2020, at 8:18 PM, Anthony Marzbanian <anthony@roof-crafters.com> wrote:

You're welcome :)

Talk to you tomorrow

Sincere thanks,

Anthony Marzbanian

<https://mail.aol.com/webmail-std/en-us/PrintMessage>

From: anthony@roof-crafters.com,

To: blurbit@aol.com,

Subject: Re: from Lorraine Yaralian:))


Date: Thu, Sep 24, 2020 5:36 pm

Attachments:




PLAIN RIDGE CAP

- X=4" LG-101
- X=5" LG-101A
- X=6" LG-101B
- X=7" LG-101C



$\frac{4}{12}$ PITCH





Historic Review Board Meeting Staff Report

From the Department of Community and Economic Development
14 October 2020

1 SUMMARY OF REQUEST

1711 King Street, Roof Replacement

Applicant: Lorraine Yaralian (20-45 HRB.1)

The applicant is requesting final approval of a roof replacement at 1711 King Street.

This is a contributing structure within the Historic Conservation Neighborhood and the Northwest Quadrant.

2 FACTS

Property Address:	1711 King Street
Parcel ID:	R120 003 000 0224 0000
Case Number:	20-45 HRB.1
Applicant:	Lorraine Yaralian
Zoning:	T4-HN
Use:	Single Family Dwelling

District Development Standards for T4-HN:

- **Setback requirements –**
 - *Front: Average prevailing setback on block.*
 - *Rear setback – 15' min.*
 - *Side Corner/Alley – 5' min. – no max.*
 - *Side Interior – 6' min.*
- **Primary Building Height:** 3 stories, max.
- **Impervious Surface Coverage:** 55% maximum
- **Frontage Buildout:** 75% maximum
- **Permitted Uses:** Single Family dwelling, or Two- or Three-Unit Dwelling is permitted by right in the T4-HN zoning classification.



References:

Secretary of the Interior's Standards for the Treatment of Historic Properties, pp. 44, 98-100
Beaufort Preservation Manual Supplement, pp. 46 – 47
Northwest Quadrant Design Principles, pp. 33 - 34

3 STAFF COMMENTS / RECOMMENDATIONS

General Considerations Regarding Roofing

1. The applicant is requesting to replace the historic standing seam metal roof at 1711 King Street with a new asphalt shingle roof due to failure of the existing historic metal panels. The applicant has proposed two options for replacement:
 - a. The first option is to replace the upper and lower roofs with Asphalt Shingle.
 - b. The second option is to replace the upper roof with Asphalt Shingle and to replace the lower “front and back low slopes” with metal standing seam.
2. Page 44 of the Secretary of the Interior’s Standards for the Treatment of Historic Properties states that the following are “not recommended” preservation techniques:
 - a. “Altering the roof and roofing materials which are important in defining the overall historic character of the building so that, as a result, the character is diminished.”
 - b. “Replacing historic roofing material instead of repairing or replacing only the deteriorated material.”
 - c. “Changing the type or color of roofing materials.”
3. Pages 98-100 of the Secretary of the Interior’s Standards for the Treatment of Historic Properties states that the following are “not recommended” rehabilitation techniques:
 - a. “Removing or substantially changing roofs which are important in defining the overall historic character of the building so that, as a result, the character is diminished.”
 - b. “Replacing an entire roof feature when repair of the historic roofing materials and limited replacement of deteriorated or missing components are feasible.”
 - c. “Removing a feature of the roof that is unrepairable and not replacing it or replacing it with a new roof feature that does not match.”
 - d. “Using a substitute material for the replacement that does not convey the same appearance of the roof covering or the surviving components of the roof feature or that is physically or chemically incompatible.”

Asphalt Roofing

4. Page 46 of the Beaufort Preservation Manual Supplement states that “Asphalt shingles are not recommended for existing historic buildings. When used for new or existing construction, they should be monochromatic (especially if replacing a metal roof), so as to lessen their visual impact.”, and page 47 of the same document recommends that existing historic roofs should be “retained and repaired.” Staff understands that the existing historic roof must be replaced (per applicant’s provided roof subcontractor’s letter), but staff does not support replacement of the historic metal standing seam roof fabric with an asphalt shingle roof.

Metal Roofing

5. Page 47 of the Beaufort Preservation Manual Supplement also states that “Preformed metal roofing panel systems are not recommended for existing historic buildings. While it is a relatively inexpensive metal roof, it is intended primarily for use on contemporary commercial structures. Its wide cap and trim pieces give it a thick and heavy appearance that is not compatible with the

massing of roofs on historical buildings. Its relatively poor longevity makes it, in the long term, no savings in comparison to the fifty-year lifetime of good quality flat or standing seam roofing.” Staff does not support option 2, the replacement of the existing historic roof on the low slope portions with a preformed metal roofing system, because its associated manufactured trim details are too large for a single family dwelling and therefore take away from the historic character of the building.

6. Page 33-34 of the Northwest Quadrant Design Principles states the following:
 - a. “Existing historic roofing should be retained and repaired wherever possible.... Within the neighborhood are several surviving historic standing seam metal roofs. Modern coatings may be applied which offer a relatively low-cost repair alternative.”
 - b. “When using metal roofing, a metal roof with a low profile is preferred.”
 - c. “A rolled seam is preferred. Traditional ridge and eave details are also preferred.”
 - d. “Other low standing seam designs are also acceptable.”
 - e. “Roofs with a taller standing seam than used traditionally or those of a corrugated design are not appropriate but may be considered on a case-by-case basis.
 - f. Prefabricated industrial roofing or modern pan roofing is not appropriate.

Staff Conclusion:

As to the request to replace all historic metal roof with asphalt shingle (option 1), Staff is not in support and recommends denial of this application. As to the request to replace the low slope portions with metal standing seam, and the rest of the historic metal roof with asphalt shingle (option 2), Staff is not in support and recommends denial of this application. Staff feels that the existing historic metal roof is a character defining feature of this property, and it must be replaced in its entirety with a hand seamed roof to maintain the historic character of the building. The field seams may be mechanically seamed, but the hips, ridges, and terminations must be hand-folded and seamed without the use of prefabricated bulky hip caps, ridge caps, and other terminations. It is the applicant/roof contractor’s responsibility to select appropriate metal roofing material suitable for hand folding at ridges, hips, and terminations

STAFF RECOMMENDATION: Denial due to conditions noted above.