

Schedule of Bid Prices						
Item No.	Spec. Section	Description	Unit	Quantity	Unit Price	Total Bid Price
1	01 00 00	Mobilization & testing	LS	1		
2	31 10 00	Testing - Verify existing line crossings (pothole) at Boundary St, complete with SCDOT lane closures and high-volume patch	LS	1		
3	31 10 00	Demolition - Remove existing concrete sidewalk complete with curbing as necessary to accommodate sewer installation (and/or sawcut as necessary for any connected monolithic curbing)	SY	37		
4	31 10 00	Demolition - Remove exist. vegetation (including all shrubs/trees within construction limits not shown on the plans)	LS	1		
5	31 10 00	Demolition - Abandon in place 8-in gravity sewer	LF	120		
6	32 10 00	Demolition - Abandon in place 6-in forcemain	LF	235		
7	-	Existing live oaks tree preservation - expose and cleanly sawcut roots with concrete saw prior to backfilling, shore sewer installation to minimize trench width adjacent to trees	LS	1		
8	32 10 00	Remove and reinstall existing site lighting system	EA	1		
9	31 10 00	Existing SCE&G pole hold, complete	LS	1		
10	31 20 00	Finish grading	SY	4500		
11	31 25 00	Silt fence	LF	493		
12	33 31 00	Sewer - Cap existing 6-in forcemain	EA	2		
13	33 31 00	Sewer - Plug existing SSMH	EA	2		
14	33 31 00	Surge SSMH "A", complete (interior coated)	EA	1		
15	33 31 00	SSMH "B", complete (interior coated)	EA	1		
16	33 31 00	SSMH "C", complete	EA	1		
17	33 31 00	SSMH "D", complete	EA	1		
18	33 31 00	SSMH "E", complete	EA	1		
19	33 31 00	SSMH "F", complete	EA	1		
20	02446	Jack and Bore: Mobilization	LS	1		
21	02446	Jack and Bore: complete with 16-in Steel Encasement	LF	110		
22	33 31 00	8-in PVC Sewer line, complete	LF	303		
23	33 31 00	6-in Forcemain, complete	LF	6		
24	33 31 00	6-in Forcemain connection & 90 degree bend, complete	LS	1		
25	31 23 23	Temporary Sewer Re-routing (to accommodate construction and system connection)	LS	1		
26	31 23 23	Flowable fill backfill - Sycamore sewer install and 6" FM/8"Gravity fill	CY	104		
27	32 92 19	Traffic Control & Signage	LS	1		
28	32 13 13	Replace 6" Concrete sidewalk complete (curbing, ramps, etc.)	SY	37		
29	32 92 19	Grassing & stabilization (St. Augustine Sod)	SF	4500		
30	01 00 00	Provide Asbuilt Survey (meeting BJWSA requirements)	LS	1		

Total Bid for project = \$ _____

Printed Name of authorized company representative: _____

Signature / Title: _____

1	ADD	2.5-in caliper Live Oak Trees - installed, complete	EA	3		
2	ADD	6-in caliper Live Oak Trees - installed, complete	EA	3		
3	ADD	Demo Existing Live Oak Trees on County Property	EA	3		